


## APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/13/2013-14, Date: 23.10.2013


Improvements Roads and Construction Culvert in Singapura Layout from Military Compound to Varadarajaswamy Layout in Ward No. 11 (Change of Work and Palce: Construction of Samudaya Bhavan to Senior Citizens near Hopcoms, Vidyaranyapura in Ward No. 9, Vidyaranyapura Sub Division).

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Unit | Approved Tender Rates of |                                                |
|---------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|------------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      | HEMADRI REDDY            |                                                |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      | In Figures               | In Words                                       |
| 1       | 8.40          | Earth work in surface excavation in Ordinary soil for levelling and lowering the ground manually ( other than foundation of buildings, culverts, road, drains and trenches of pipes lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m excavated surface levelled and neatly dressed earth to be levelled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work. | Cum  | 130.00                   | Rupees One Hundred Thirty Only                 |
| 2       | 45.28         | Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods etc complete as per specifications and directions of engineer in charge of the work.                            | Cum  | 230.00                   | Rupees Two Hundred Thirty Only                 |
| 3       | 4.88          | Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.                    | Cum  | 4400.00                  | Rupees Four Thousand Four Hundred Only         |
| 4       | 12.09         | Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                        | Cum  | 3850.00                  | Rupees Three Thousand Eight Hundred Fifty Only |
| 5       | 6.21          | Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                   | Cum  | 4450.00                  | Rupees Four Thousand Four Hundred Fifty Only   |
| 6       | 45.28         | Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                       | Cum  | 115.00                   | Rupees One Hundred Fifteen Only                |
| 7       | 13.08         | Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                   | Sqm  | 90.00                    | Rupees Ninety Only                             |
| 8       | 20.56         | Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                 | Cum  | 6150.00                  | Rupees Six Thousand One Hundred Fifty Only     |


| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Unit | Approved Tender Rates of |                                                    |
|---------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|----------------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | HEMADRI REDDY            |                                                    |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | In Figures               | In Words                                           |
| 9       | 30.68         | Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts conforming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                   | Cum  | 5800.00                  | Rupees Five Thousand Eight Hundred Only            |
| 10      | 4.77          | Providing and laying in position reinforced cement concrete of mix M20 with OPC cement @ 24kgs, with 12 mm and down size graded granite metal coarse aggregates @ 0.5175 cum and fine aggregates @ 0.345 cum with superplasticiser @ 0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Sqm  | 450.00                   | Rupees Four Hundred Fifty Only                     |
| 11      | 38.37         | Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery TMT Bars Fe 550 etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qtl  | 7600.00                  | Rupees Seven Thousand Six Hundred Only             |
| 12      | 55.66         | Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc, consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75kg/sqm conforming admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment, (b) laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junction of walls and slabs, (c) after two days of proper curing, applying a second coat of cement slurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 3000x3000mm square, (e) the whole | Sqm  | 855.00                   | Rupees Eight Hundred Fifty Five Only               |
| 13      | 55.66         | Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Sqm  | 185.05                   | Rupees One Hundred Eighty Five and Five Paise Only |

  
**Executive Engineer**  
 Byatarayanapura Division  
 Yelahanka Zone, B.S.M.P.  
 Bangalore - 560 092

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                               | Unit | Approved Tender Rates of |                                      |
|---------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|--------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                           |      | HEMADRI REDDY            |                                      |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                           |      | In Figures               | In Words                             |
| 14      | 108.48        | Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                     | Sqm  | 200.00                   | Rupees Two Hundred Only              |
| 15      | 164.14        | Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                             | Sqm  | 28.00                    | Rupees Twenty Eight Only             |
| 16      | 107.79        | Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                       | Sqm  | 175.00                   | Rupees One Hundred Seventy Five Only |
| 17      | 48.87         | Providing and laying flooring with M15 cement concrete, 40mm thick using broken granite metal of 20mm and down size laid to line and level in one layer and finish with a floating coat of neat cement , including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.                                                                 | Sqm  | 300.00                   | Rupees Three Hundred Only            |
| 18      | 44.21         | Flooring with 25mm to 40mm thick polished Thandur blue stone slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc complete as per specifications and directions of engineer in charge of the work. | Sqm  | 1100.00                  | Rupees One Thousand One Hundred Only |
| 19      | 41.61         | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.                                                                      | Sqm  | 290.00                   | Rupees Two Hundred Ninety Only       |
| 20      | 4.77          | Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                           | Sqm  | 250.00                   | Rupees Two Hundred Fifty Only        |
| 21      | 79.22         | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.                                                                                                               | Sqm  | 225.00                   | Rupees Two Hundred Twenty Five Only  |

  
**Executive Engineer**  
 Byatarayanapura Division  
 Yelahanka Zone, B.B.M.P.  
 Bangalore - 560 092


| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Unit | Approved Tender Rates of |                                          |
|---------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      | HEMADRI REDDY            |                                          |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      | In Figures               | In Words                                 |
| 22      | 4.41          | Supply and fixing pressed steel door frames size 125x65 mm manufacture from 1.25mm thick carbon steel or imported steel strips with mitred joints of 90° for door openings and shutters made out of seasoned honne wood, styles of 30mm, thick with lock rail of 160mm, width, top and side rails of 100mm, width width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formaldehyde resin and the shutter shall be not proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years, this shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting with enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc, complete the hollow portion of the frame to be filled with cement concrete 1:2:4. etc complete as per specifications and directions of engineer in charge of the work.                                                                                             | Sqm  | 3900.00                  | Rupees Three Thousand Nine Hundred Only  |
| 23      | 4.59          | "Supplying and fixing pressed steel window frame of size 100x50mm manufacture from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 90° for window openings and shall be suitable to fix M.S grills as per design and drawings using 12mm dia rods at 100mm centre to centre horizontally and two members of M.S flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S flats with 16mm size lugs, and 8nos, of 100mm size hinger, 4nos of butt stay pins and 4nos, tower bolts and shutters half paneled and half glazed with shutters made out of seasoned honne wood, styles of 30mm thick and 100 mm width and rails of 30mm thick and 100 mm width and using 4mm thick pin headed glass and panel, filling with 12mm thick particle board of exterior grade bonded with phenol formaldehyde resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years, this shall be as per approved drawing, specification and direction including cost of conveyance, manufacturing painting with 2 coats enamel paint over one coat of primer, cost of labour | Sqm  | 4300.00                  | Rupees Four Thousand Three Hundred Only  |
| 24      | 164.14        | Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Sqm  | 65.00                    | Rupees Sixty Five Only                   |
| 25      | 107.79        | Providing and finishing external walls in two coats with water proof cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work. with Primer                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Cum  | 80.00                    | Rupees Eighty Only                       |
| 26      | 1.00          | Providing and fixing white vitreous china clay, flat back wash basin of size 630x450mm with pair of 15mm C.P brass pillar taps with C.I./M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Unit | 3800.00                  | Rupees Three Thousand Eight Hundred Only |

  
**Executive Engineer**  
 Byataraynapura Division  
 Yelahanka Zone, B.R. 12,  
 Bangalore - 560 092

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                            | Unit | Approved Tender Rates of |                                        |
|---------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|----------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | HEMADRI REDDY            |                                        |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | In Figures               | In Words                               |
| 27      | 30.00         | Providing and fixing to wall, ceiling and floor, low density polyethylene pipes kgs/sq.cm working pressure 32mm outside diameter, compression type fittings, wall clips, making good the wall ceiling and floor cost of materials, labour charges HOM of equipments and testing excluding cost of fittings, etc complete as per specifications and directions of engineer in charge of the work.                                       | Rmtr | 170.00                   | Rupees One Hundred Seventy Only        |
| 28      | 1000.00       | Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer black of blue and inner white layer of approved quality and make, conforming etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                   | L    | 7.00                     | Rupees Seven Only                      |
| 29      | 4.00          | Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                | Each | 200.00                   | Rupees Two Hundred Only                |
| 30      | 2.25          | Providing colour glazed tiles of size 10mm thick for flooring, treads of steps and landing, laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing using white cement with matching colour pigment, including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.                                                                                              | Sqm  | 900.00                   | Rupees Nine Hundred Only               |
| 31      | 9.84          | Providing skirting, dado, rises of steps with Colour glazed tiles 15x15cms 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, etc complete as per specifications and directions of engineer in charge of the work. | Sqm  | 950.00                   | Rupees Nine Hundred Fifty Only         |
| 32      | 35.00         | Providing and fixing in wall surface 4 kg/sq.cm H.D.P.E. rain down water pipes 90 mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.                                                                                     | m    | 460.00                   | Rupees Four Hundred Sixty Only         |
| 33      | 1.00          | Square Tank Cover "ISI" marked 24'x24'x pf 100kg in weight Page No. XXXI ) etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                        | L/S  | 5400.00                  | Rupees Five Thousand Four Hundred Only |
| 34      | 45.00         | Groove Cutting : Supplying ... dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary 32 mm dia 2.5mm thick etc complete as per specifications and directions of engineer in charge of the work.                    | Mtrs | 70.00                    | Rupees Seventy Only                    |
| 35      | 2.00          | Supplying and flush mounting teak wooden box with out front plank made of not less than 12mm thick wood after due groove cutting necessary masonry patch work 10"X7"X3" (300X228X76mm) etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                            | Each | 70.00                    | Rupees Seventy Only                    |
| 36      | 2.00          | 8"X6"X3" (300X228X76mm)                                                                                                                                                                                                                                                                                                                                                                                                                | Each | 55.00                    | Rupees Fifty Five Only                 |
| 37      | 12.00         | Supplying and fixing PVC/metal conduit accessories special type Junction Box 32 mm Junction Box etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                   | Each | 30.00                    | Rupees Thirty Only                     |
| 38      | 4.00          | Deep 32 mm Junction Box                                                                                                                                                                                                                                                                                                                                                                                                                | Each | 35.00                    | Rupees Thirty Five Only                |
| 39      | 4.00          | Fan Box 18 /SWG                                                                                                                                                                                                                                                                                                                                                                                                                        | Each | 60.00                    | Rupees Sixty Only                      |

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Unit | Approved Tender Rates of |                                      |
|---------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|--------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      | HEMADRI REDDY            |                                      |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      | In Figures               | In Words                             |
| 40      | 4.00          | Point Wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using Copper PVC insulated multi strand 2x1.5 Sqmm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet gang box the other end of the wires shall be terminated with sufficient loose length in a wood PVC round block complete for each outlet KPWD SR 2010-11 (P.3/I.8) Point Wiring using Class A Materials a) Short point upto 3Mtr from tapping point to out let via switch etc complete as per specifications and directions of engineer in charge of the work. | Each | 180.00                   | Rupees One Hundred Eighty Only       |
| 41      | 4.00          | b) Medium point above 3mtr upto 6mtr from tapping point to out let via switch                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Each | 260.00                   | Rupees Two Hundred Sixty Only        |
| 42      | 3.00          | C) Long point above 6mtrs upto 10mtrs from tapping point to outlet via switch                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Each | 370.00                   | Rupees Three Hundred Seventy Only    |
| 43      | 2.00          | Supplying and fixing superior quality modula switch mounting polyorbonate plate with ncessary supporting back plate with required nos. of machines screwes, bolts nuts etc., complete on the existing metal/PVC box 1 to 3 Modular etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                            | Each | 85.00                    | Rupees Eighty Five Only              |
| 44      | 2.00          | 8 Modular                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Each | 175.00                   | Rupees One Hundred Seventy Five Only |
| 45      | 15.00         | Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plat 6Amps one way. etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                                                               | Each | 96.00                    | Rupees Ninety Six Only               |
| 46      | 6.00          | 6Amps 3way Socket.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Each | 165.00                   | Rupees One Hundred Sixty Five Only   |
| 47      | 4.00          | Stepped Fan Regulator                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Each | 520.00                   | Rupees Five Hundred Twenty Only      |
| 48      | 6.00          | Supply patty type fluorescent tube light fitting of 4' - 36/40 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking, locking type brass contact holder mounted on double fold type sheet base fully wired for used on 230 Volts A C Supply including fluourescent tube Group 'A' etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                    | Each | 380.00                   | Rupees Three Hundred Eighty Only     |
| 49      | 5.00          | Supplying of Incandescent lamps C75B.C. 100Watts                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Each | 15.00                    | Rupees Fifteen Only                  |
| 50      | 4.00          | Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system KPWD SR 2010-11 (P-23, I-23) Regulator Model (Khaitan, Crompton Geaves, Orient, Polar, Bajaj, Usha, Havells, Almonard 56" Sweep (1400 mm)                                                                                                                                                                                                                                                                                 | Each | 2000.00                  | Rupees Two Thousand Only             |
| 51      | 1.00          | Supplying and fixing 32Amps security and energy savings DP switch with key tag suitable to operate on 230 Volts 50Hz AC supply & completely wired on existing box KPWD SR 2010-11 (P.9/I.19) Group A                                                                                                                                                                                                                                                                                                                                                                                                                                               | Each | 630.00                   | Rupees Six Hundred Thirty Only       |
| 52      | 1.00          | Supplying an fixing one of 230 volts PBBC bakelite staight or slant batten holder and wiring with in 60w/230 Volts lamps KPWD SR 2010-11 (P-13, I.2)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | No   | 60.00                    | Rupees Sixty Only                    |

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Unit | Approved Tender Rates of |                                             |
|---------|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|---------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      | HEMADRI REDDY            |                                             |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      | In Figures               | In Words                                    |
| 53      | 1.00          | Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required 5-32 Amps SP KPWD SR 2010-11 (P.34/I.13)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Each | 560.00                   | Rupees Five Hundred Sixty Only              |
| 54      | 1.00          | Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc KPWD SR 2010-11 (P.32/I.2) 20"x20"x2.5"                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Each | 285.00                   | Rupees Two Hundred Eighty Five Only         |
| 55      | 1.00          | Supplying and fixing of porcelain fuse channel with cut out on existing wooden /panel using necessary nuts, bolts and washers etc complete KPWD SR 2010-11 (P.30/I.3) 32 Amps etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Each | 100.00                   | Rupees One Hundred Only                     |
| 56      | 1.00          | Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipment on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit. The pit should be filled with equal proportion of salt and charcol 150mm around the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per ISI specification 7.3.3 of Is 732 using 12mm dia nuts, washers and checknuts etc the pipe shall have 16 through holes of 122 mm dia etc complete as per specifications and directions of engineer in charge of the work.                                                                                                                                                                                                                                                                                    | No   | 1950.00                  | Rupees One Thousand Nine Hundred Fifty Only |
| 57      | 10.00         | INSULATED CABLE ON MESSENGER WIRE Using 2 single core wires for a single phase and 4 single core wires for 3 phase supplying and stringing PVC insulated and PVC sheathed 650/1100V class aluminium conductor of size supported by 3.15mm (10 SWG) GI messenger wire with two breaks insulators, one at each end of the span with suspenders at intervals of 0.75m. Each suspender shall be of porcelain reel insulator of suitable core through which insulated wire passes (single core or twin core as the case may be) and this reel insulator shall be fixed to the messenger wire using 2mm (No. 14SWG) GI wire suitably bent and twisted. Separate reel insulator shall be provided for each wire the messenger wire shall be bed-ended on the clamp provided to the departmental pole vide item No. 4 above c) 6 Sqmm etc complete as per specifications and directions of engineer in charge of the work. | Mtr  | 45.00                    | Rupees Forty Five Only                      |



Signature of the Contractor



Executive Engineer  
Byarayanapura Division  
BBMP, Bangalore - 92